

भा.कृ.अनु.प. – केंद्रिय रोपन फसल अनुसंधान संस्थान ICAR-CENTRAL PLANTATION CROPS RESEARCH INSTITUTE (भारतियकृषिअनुसंधानपरिषद) (Indian Council of Agricultural Research) अनुसंधानकेंद्रकाहिकुचि,गुवाहाटि-७८१०१७,आसाम। Research Centre Kahikuchi, Guwahati – 781 017, Assam.



TeleFax: 0361-2841785, Ph.0361-2840251, Email:sicrckahikuchi.cpcri@icar.gov.in&sickahikuchi@yahoo.com

No.F.4 (20)/2013-Works.

Dated: 01.01.2018.

SHORT TENDER NOTICE

Sealed Quotations (two bid system) are hereby invited from reputed and registered contractors/firms for "Repair and maintenance of boundary wall and entrance gate of farm campus include replacement of damaged barbed wire fencing" at this centre and conform to the following terms and conditions. Details of the work is given below:

Sl. No.	Description of works	Quantity/Area		
01.	Repair and maintenance of boundary wall and entrance gate of farm campus including replacement of damaged barbed wire fencing as per schedule of items in the pres cribbed proforma.	·		

Completion of works: 01 month.

Rate: Item wise rates may be quoted in the prescribed form available with the office/website.

Specifications: As per CPWD specification and as per local practices.

Terms and Conditions.

- 01. Quotation should be submitted in two bid system, Technical bid and financial bid separately and put together in a big cover super scribed as "Repair and maintenance of boundary wall and entrance gate of farm campus including replacement of damaged barbed wire fencing".
- 02. Technical bid should contain checklist, application and all relevant documents including EMD. Demand Draft No. should be mentioned on top of the envelope of main cover, otherwise the quotation will not be opened.
- 03. Financial bids of the successful technical bidders will only be opened.
- 04. The rate should be quoted **per unit** basis both in figure and words for neach item in the schedule.
- 05. The rate quoted should be valid for a minimum period of 90 days from the receipt of the quotation.
- 06. EMD @2% of the quoted amount in the form of DD in favour of ICAR Unit, CPCRI, Kasaragod payable at SBI, Kasaragod (Code-06715) should be furnished along with Technical bid of the quotation.

- 07. Successful contractor/firm will have to deposit **performance security @** 10% of the total amount, otherwise work will not be awarded and EMD will be forfeited.
- 08. The work should be executed strictly as per specifications and under the supervision of the authorized officials.
- 09. The work should be taken up and completed as per schedule on receipt of the work order.
- 10. The right to reject all or part of the quotation without assigning any reason is reserved with the undersigned and no complaint in this regard will be entertained.
- 11. The work will be checked and measured by the person authorized by this centre and his decision with concurrence of the Scientist-in-charge shall be final.
- 12. The undersigned reserves the right to cancel the work order at any stage, if not found satisfactory. The decision of the Scientist-in-charge regarding the work will be final and no other claims shall be entertained.
- 13. Payment will be made only after satisfactory completion of the whole work. No advance or part payment is admissible as per our rules.
- 14. Copy of Labour Licence, Registration Certificate, GST Certificate, Civil works certificate of the firm under the work contract of the Govt. of Assam, PAN Card Number should be submitted along with quotation otherwise the quotation will be rejected.
- 15. Sealed quotations superscribed (two bid system) are hereby invited from the reputed and registered contractors/firms for "Repair and maintenance of boundary wall and entrance gate of farm campus including replacement of damaged barbed wire fencing" should reach the undersigned on or before 16.01.2018.01.2018 up to 02.00 PM Technical bid will be opened on 16.01.2018 at 03.00 PM in the presence of interested tenderers if any.

2017, 1.18

NOTICE BOARD FOR CIRCULATION.

Institute website for wide circulation.

वैज्ञानिक प्रभारी **Signifies** in Abatage के:रो.फ.अ.सं. अनुसंधान केन्द्र C.P.C.R.I., Research Centre Kahikuchi, Guwahati-781017 काहिकुची, गुवाहाटी-781017 असम / Assam

Copy to:

- 01. The Librarian & Information Officer, ICAR-CPCRI, Kasaragod-671 124, Kerala State with a request to please upload the content in the institute website.
- 02. Dr. Thamban C., (Contact Officer for RC, Kahikuchi) Principal Scientist & Acting Head, Divn. Of social Science, ICAR-CPCRI, Kasaragod-671 124, Kerala State.

FINANCIAL BID

(This financial bid to be enclosed in a separate envelope with seal)

Last date for receipt of tender

16.01.2018 up to 02.00 PM.

Date of opening of financial bid

16.01.2018 at 03.00 PM.

Τo,

The Scientist-in-charge, ICAR-CPCRI, RC, Kahikuchi, Guwahai-781 017, Assam.

Sir,

I/We wish to submit our Tender for "**Repair and maintenance of boundary wall and entrance gate of farm campus including replacement of damaged barbed wire fencing**" at ICAR-Central Plantation Crops Research Institute, Research Centre, Kahikuchi, Guwahati -781 017, Assam.

SI. No.	Particulars/details	Quantity/ Area	Rate	Amount
01	Repair and maintenance of boundary wall and entrance gate of farm campus including replacement of damaged barbed wire fencing as per abstract of estimate with weight of 9.38kg/100mtrfor enter length of existing barbed wire portion. The existing angle iron fencing post will be painted with zinc chromatic anti corrosive metal primer and two coat of synthetic enamel paint to be applied. Estimates includes one coat of distemper painting to the inside portion of watchman shed and two coat of exterior emulsion painting is included for the boundary wall and watchmen shed exterior portion.	As per annexure	As per enclosed annexure	As per enclosed annexure
	TOTAL:		5	-

(Rupees

only)

Note:

01. The rates are to be quoted inclusive of all charges/taxes/profits.

Yours faithfully

Signature:

Name:

Address:

ANNEXURE- II

<u>Tender for</u> "Repair and maintenance of boundary wall and entrance gate of farm campus including replacement of damaged barbed wire fencing".

Name of the participating Firm/Agency_____

CHECK LIST

YES/NO

01	Tender document duly filled and signed
02	Covering letter (application) furnished with the tender document
03	Demand Draft for Earnest Money Deposit @ of 2% of the amount quoted
04	Registration certificates of the firm under the work contract of the Govt. or the contractor/agency must have a registration with the Contract Labour (Regulation and Abolition) Act. 1970. The contractor shall obtain the labour license under this Act.
05	PAN/TAN Number and a copy of latest Income Tax Return
06	GST Certificate should be furnished with the tender document
07	Civil works certificate should be furnished with the tender document along with last 3 years certificate.
08	Credential document list submitted

भा.कृ.अनु.प. – केंद्रिय रोपन फसल अनुसंधान संस्थान ICAR-CENTRAL PLANTATION CROPS RESEARCH INSTITUTE (भारतियकृषिअनुसंधानपरिषद) (Indian Council of Agricultural Research) अनुसंधानकेंद्रकाहिकुचि, गुवाहाटि-७८१०१७,आसाम।

NAME OF THE WORK: - REPAR & MANTENANCE OF BOUNDARY WALL AND ENTRANCE GATE OF FARM CAMPUS INCLUDING REPLACEMENT OF DAMAGED BARBED WIRE FENCING AT CPCRI, RC, KAHIKUCHI.

Research Centre Kahikuchi, Guwahati - 781 017, Assam.

SCHEDULE OF ITEM WISE WORK

Item	Description of work	Unit	Approx	Rate	Amount
01	Dismantling barbed wire or flexible wire rope fencing including				
	making rolls and stacking within 50 meters lead.				
	Specification No.15.36, Page No.224, DSR.	Kg	343		
02	Painting Steel work with Deluxe Multi Surface Paint to give an even				
	shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat				
2	of Zinc chromatic primer applied @ 0.80 ltr/10 sqm of approved brand	Sqint	31		
	and manufacture.		-15		
	Specification No.13.48.3, Page No.220, DSR 2014.				
03	Providing and fixing G.I barbed fencing to the Existing Angle iron				
	post with horizontal lines and two diagonals interwoven with				
	horizontal wires, of barbed wire weighing 9.38 kg per 100 m	metre	3810		
	(minimum), between the two posts fitted and fixed with G.I staples,				
	turn buckles etc. complete.				
	Specification No.16.18.1, Page No.258, DSR.				
04	Finishing the wall with Premium acrylic smooth exterior paint with		2		
	silicone additives of required shade Two or more coats @ 1.67				
	liters/10 square meter applied over existing surface (Approved				
	brand). The work shall include cleaning the wall, crack filling,	Sqmt	166		
	finishing with plaster of paris/white cement etc. The rate shall include				
	cost and conveyance of all materials, labour, scaffolding, cleaning				
	paint stains from floor, wall and glass etc. completely as directed.				
	Specification No.14.66.1, DSR 14.				

3. 31-7.1817- X					05	
A THE TRANSPORT		One or more coat Specification No.14.45-1, Page No.235, DSR 14.	all materials, labour, scaffolding, cleaning paint stains from floor, wall and glass etc. completely as directed.	include/cleaning the wall, crack filling, finishing with plaster of paris/white cement etc. The rate shall include cost and conveyance of	Distempering the wall with oil bound washable distemper of approved brand and manufacture of required shade and colour. The work shall	
	Total Amount			Sqmt 17		
Signature of the Firm/Agency with seal Full Address						