



भा.कृ.अनु.प. – केंद्रिय रोपन फसल अनुसंधान संस्थान
ICAR-CENTRAL PLANTATION CROPS RESEARCH INSTITUTE
(भारतियकृषिअनुसंधानपरिषद)

(Indian Council of Agricultural Research)

अनुसंधानकेंद्रकाहिकुचि, गुवाहाटी-७८१०१७, आसाम।

Research Centre Kahikuchi, Guwahati – 781 017, Assam.



TeleFax: 0361-2841785, Ph.0361-2840251, Email:sicrckahikuchi.cpcri@icar.gov.in&sickahikuchi@yahoo.com

No.F.4 (20)/2013-Works.

Dated: 01.01.2018.

SHORT TENDER NOTICE

Sealed Quotations (two bid system) are hereby invited from the reputed and registered contractors/firms for **“Repair and maintenance of drainage system behind old Type-II quarters”** of this centre and conform to the following terms and conditions. Details of the work given below:

Sl. No.	Description of works	Quantity/Area
01.	Repair and maintenance of drainage system behind old Type-II quarters. The existing damaged drain to be repaired as per schedule of items.	As per annexure/ Schedule of items

Completion of works: 01 month.

Rate: Item wise rates may be quoted in the prescribed form available with the office/website.

Specifications: As per CPWD specification and s per local practices.

Terms and Conditions.

01. Quotation should be submitted in two bid system, Technical bid and financial bid separately and put together in a big cover scribed as **“Repair and maintenance of drainage system behind old Type-II quarters”**.
02. Technical bid should contain checklist, application and all relevant documents including EMD. Demand Draft No. should be mentioned on top of the envelope of main cover, otherwise the quotation will not be opened.
03. Financial bids of the successful technical bidders will only be opened.
04. The rate should be quoted **per unit** basis both in figure and words.
05. The rate quoted should be valid for a minimum period of 90 days from the receipt of the quotation.
06. **EMD @2%** of the quoted amount in the form of DD in favour of ICAR Unit, CPCRI, Kasaragod payable at SBI, Kasaragod (Code-06715) should be furnished along with Technical bid of the quotation.
07. Successful contractor/firm will have to deposit **performance security @ 10%** of the total amount, otherwise work will not be awarded and EMD will be forfeited.
08. The work should be executed strictly as per specifications and under the supervision of the authorized officials.


07. Successful contractor/firm will have to deposit **performance security @ 10%** of the total amount, otherwise work will not be awarded and EMD will be forfeited.
08. The work should be executed strictly as per specifications and under the supervision of the authorized officials.
09. The work should be taken up and completed as per schedule on receipt of the work order.
10. The right to reject all or part of the quotation without assigning any reason is reserved with the undersigned and no complaint in this regard will be entertained.
11. The work will be checked and measured by the person authorized by this centre and his decision with concurrence of the Scientist-in-charge shall be final.
12. The undersigned reserves the right to cancel the work order at any stage, if not found satisfactory. The decision of the Scientist-in-charge regarding the work will be final and no other claims shall be entertained.
13. Payment will be made only after satisfactory completion of the whole work. No advance or part payment is admissible as per our rules.
14. Copy of Labour Licence, Registration Certificate, GST Certificate, Civil works certificate of the firm under the work contract of the Govt. of Assam, PAN Card Number should be submitted along with quotation otherwise the quotation will be rejected.
15. Sealed quotations superscribed (two bid system) are hereby invited from the reputed and registered contractors/firms for **“Repair and maintenance of drainage system behind old Type-II quarters”** should reach the undersigned on or before **16.01.2018 up to 02.00 PM** Technical bid will be opened on **16.01.2018 at 03.00 PM** in the presence of interested tenderers if any.

NOTICE BOARD FOR CIRCULATION.

Institute website for wide circulation.

Copy to:

03. The Librarian & Information Officer, ICAR-CPCRI, Kasaragod-671 124, Kerala State with a request to please upload the content in the institute website.
04. Dr. Thamban C., (Contact Officer for RC, Kahikuchi) Principal Scientist & Acting Head, Divn. Of social Science, ICAR-CPCRI, Kasaragod-671 124, Kerala State.


 वैज्ञानिक प्रभारी / Scientist-in-charge
 के.रो.फ.अ.सं. अनुसंधान केन्द्र
 C.P.C.R.I., Research Centre
 Kahikuchi, Guwahati-781017
 काहिकुची, गुवाहाटी-781017
 असम / Assam

FINANCIAL BID

(This financial bid to be enclosed in a separate envelope with seal)

Last date for receipt of tender : 16.01.2018 up to 02.00 PM.

Date of opening of financial bid : 16.01.2018 at 03.00 PM.

To,

The Scientist-in-charge,
ICAR-CPCRI, RC, Kahikuchi,
Guwahai-781 017, Assam.

Sir,

I/We wish to submit our Tender for **“Repair and maintenance of drainage system behind old Type-II quarters”** at ICAR-Central Plantation Crops Research Institute, Research Centre, Kahikuchi, Guwahati -781 017, Assam.

Sl. No.	Particulars/details	Quantity/ Area	Rate	Amount
01	Repair and maintenance of drainage system behind old Type-II quarters. The existing damaged drain to be repaired and extended up to major drainage line passing side by the chain linked fencing of Type-II quarters	As per annexure	As per enclosed annexure	As per enclosed annexure
TOTAL:				

(Rupees _____ only)

Note:

16. The rates are to be quoted inclusive of all charges/taxes/profits.

Yours faithfully

Signature:

Name:

Address:

ANNEXURE- II

Tender for “Repair and maintenance of drainage system behind old Type-II quarters”.

Name of the participating Firm/Agency _____

CHECK LIST

YES/NO

01	Tender document duly filled and signed	
02	Covering letter (application) furnished with the tender document	
03	Demand Draft for Earnest Money Deposit @ of 2% of the amount quoted	
04	Registration certificates of the firm under the work contract of the Govt. or the contractor/agency must have a registration with the Contract Labour (Regulation and Abolition) Act. 1970. The contractor shall obtain the labour license under this Act.	
05	PAN/TAN Number and a copy of latest Income Tax Return	
06	GST Certificate should be furnished with the tender document	
07	Civil works certificate should be furnished with the tender document along with last 3 years certificate.	
08	Credential document list submitted	

भा.कृ.अनु.प. - केंद्रीय रोपन फसल अनुसंधान संस्थान
ICAR-CENTRAL PLANTATION CROPS RESEARCH INSTITUTE
(भारतीयकृषिअनुसंधानपरिषद्)

(Indian Council of Agricultural Research)


अनुसंधानकेंद्रकाहिकुचि, गुवाहाटी-७८१०१७, आसाम।

Research Centre, Kahikuchi, Guwahati – 781 017, Assam.

NAME OF THE WORK: - REPAIR AND MAINTENANCE OF DRAINAGE SYSTEM BEHIND OLD TYPE-II QUARTERS AT CPCRI, RC, KAHIKUCHI.

SCHEDULE OF ITEM WISE WORK

Sl. No.	Description of work	Unit	Approx quantity	Rate	Amount
01	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. Specification No.2.8.1, Page No.72, DSR 2014	Cumt	6.00		
02	Providing and laying cement concrete bed 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate using 40 mm downsize jelly and clean sieved approved sand and to the sides of the precast pillars. The rate shall include cost and conveyance of all materials, erecting the pillar to true plum. Specification No.4. 1.8, Page No.85, DSR 2014	Cumt	1.00		
03	Brick work with common burnt clay F.P.S. (non Modular) bricks of class designation 7.5 in foundation and plinth in: 60101 Cement mortar 1:4 (1 cement: 4 coarse sand) Specification No.6.1.1, Page No.111, DSR 2014	Cumt	2.00		
04	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm thick with 20 mm nominal size stone aggregate. Specification No.11.3, DSR 2014	Sqmt	6.00		
05	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:3 (1 cement: 3 fine sand) Specification No.13.7.1, Page No.216 DSR 2014	Sqm	35		
Total Amount					



Signature of the Firm/Agency with seal

Full Address _____